


15-135-20486-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County, Sec. 12 Twp. 18S Rge. 24W (E) (W)
Location as "NE/CNW&SW" or footage from lines. SE SE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Leiker Well No. 2
Office Address P. O. Box 18412, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-3 19 71
Application for plugging filed 10-3 19 71
Application for plugging approved 10-3 19 71
Plugging commenced 10-3 19 71
Plugging completed 10-3 19 71
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4336 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	330'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with heavy mud to 600', plug, 70 sacks cement.
Mud to 300', 20 sacks cement. Mud to 40', plug, 10 sacks
cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Don Gardner (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Suite 250, 200 West Douglas, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of October, 19 71

My commission expires December 14, 1973

[Signature] Notary Public.

15-135-20486-0000

DRILLERS LOG

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1971
CONSERVATION DIVISION
Wichita, Kansas

#2 LEIKER
SE SE Section 12-18S-24W
Ness County, Kansas

OPERATOR: Thunderbird Drilling, Inc.
P. O. Box 18412
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
Suite 250, 200 West Douglas
Wichita, Kansas

COMMENCED: September 25, 1971

COMPLETED: October 3, 1971

CASING RECORD: 8-5/8" @ 330' w/235' sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	335	Clay and blue shale
335	937	Shale
937	948	Anhydrite
948	1050	Shale and red bed
1050	1285	Sand
1285	1579	Red bed
1579	1629	Anhydrite
1629	1893	Shale
1893	2576	Shale and lime
2576	3745	Lime and shale
3745	4336	Lime
4336		Rotary Total Depth

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.


Don Gardner

Subscribed and sworn to before me this 4th day of October, 1971.

My commission expires:
December 14, 1973


Notary Public