

15-135-20465-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ness County, Sec. 12 Twp. 18 Rge. 24W (E) (W)

Location as "NE/CNW/SE" or footage from lines C NW SE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Leiker #1 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10/23/73 19
Plugging completed 10/26/73 19
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 4355 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	329	none
				5 1/2"	4346	2206'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4300', pushed plug to 4000' and ran 10' sand and 5 sacks cement. Loaded hole, shot pipe at 2803', 2652', 2503', 2361', 2208', pulled 73 joints. Allied pumped 3 sacks hulls, 25 sacks gel and 90 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of October, 1973

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975



Notary Public.

15-135-20465-0000



RADIATION-GUARD LOG

COMPANY WELL FIELD County State	COMPANY <u>THUNDERBIRD DRILLING &</u>	
	<u>PETROLEUM RESOURCES</u>	
	WELL <u>LEIKER # 1</u>	
	FIELD _____	
COUNTY <u>NESS</u> STATE <u>KANSAS</u>		
Location <u>C-NW-SE</u>		Other Services: <u>MSG-FF</u>
Sec. <u>12</u> Twp <u>18^s</u> Rge <u>24^w</u>		
Permanent Datum <u>GROUND LEVEL</u> Elev. <u>2327'</u>		Elev.: K.B. <u>2332'</u>
Log Measured From <u>KELLY BUSHING</u> Ft. Above Perm. Datum		D.F. <u>2329'</u>
Drilling Measured From <u>KELLY BUSHING</u>		G.I. <u>2327'</u>
Date	<u>8-21-71</u>	
Run No. <u>ONE</u>	<u>GAMMA NEUTRON GUARD</u>	
Depth-Driller	<u>4355'</u>	
Depth-Welex	<u>4354'</u>	
Btm. Log Inter.	<u>4352'</u>	<u>4354'</u>
Top Log Inter.	<u>3500'</u>	<u>3500'</u>
Casing-Driller	<u>8 5/8" @ 329'</u>	@
Casing-Welex		@
Bit Size	<u>7 7/8"</u>	
Type Fluid in Hole	<u>WATER BASE</u>	
	<u>SALT MUD</u>	
Dens. Visc.	<u>10 42</u>	
pH Fluid Loss	<u>6 0.2 ml</u>	ml
Source of Sample	<u>FLOW LINE</u>	
R _{int} @ Meas. Temp.	<u>.3 @ 80°F</u>	@ °F
R _{int} @ Meas. Temp.	<u>.21 @ 80°F</u>	@ °F
R _{int} @ Meas. Temp.	<u>.45 @ 80°F</u>	@ °F
Source R _{int} R _{int}	<u>M IM</u>	
R _{int} @ BHT	<u>.21 @ 113°F</u>	@ °F
Time Since Circ.	<u>2 HRS</u>	
Max. Rec. Temp.	<u>113°F @ TD</u>	°F @
Equip. Location	<u>68701G.B.</u>	
Recorded By	<u>WEBSTER & PEBLEY</u>	
Witnessed By	<u>MR. McCALEB</u>	

STATE RECEIVED
CORPORATION COMMISSION
OCT 23 1973
CONSERVATION DIVISION
Topeka, Kansas