

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15,135-22,039-0000

LEASE NAME Levan

WELL NUMBER #1

3960 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 12 TWP. 18 RGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-1-88

Plugging Completed 7-12-88

LEASE OPERATOR Palomino Petroleum

ADDRESS Rt. #5, Box 51-C-Newton, Ks. 67114

PHONE (316-283-0232) OPERATORS LICENSE NO. 5161

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	327'	None
				4-1/2"	4390'	432.95'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Dumped sand to 4300' and 4 sacks cement. Shot casing at 3500', 3000', 2000', 800', 600' and 400'. Pulled 11 joints of 4-1/2" casing. Allied squeezed well with 175 sacks ATL cement. Maximum pressure was 500 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 88

Iona M. Leatherman  
Notary Public

My Commission Expires \_\_\_\_\_

STATE NOTARY PUBLIC  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-91