

15-135-20778-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 12 Twp. 18S Rge. 24W (E) (W)
Location as "NE/CNW/SW" or footage from lines. S/2 SE SW
Lease Owner Thunderbird Drilling, Inc.
Lease Name Anspaugh Well No. 2
Office Address P. O. Box 18412, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 8 19 73
Application for plugging filed August 8 19 73
Application for plugging approved August 8 19 73
Plugging commenced August 8 19 73
Plugging completed August 8 19 73
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4441 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	340'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 650' - 70 sacks cement; mud to 240' - 20 sacks cement; plug - 1/4 sack hulls; mud to 40' - 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don Gardner (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Suite 250, 200 West Douglas, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 73

March Day
Notary Public.

My commission expires December 14, 1973

15-135-20778-0000

DRILLERS LOG

#2 ANSPAUGH
S/2 SE SW Section 12-18S-24W
Ness County, Kansas

OPERATOR: Thunderbird Drilling, Inc.
P. O. Box 18412
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
Suite 250, 200 West Douglas
Wichita, Kansas 67202

COMMENCED: July 30, 1973

COMPLETED: August 8, 1973

CASING RECORD: 8-5/8" @ 340' w/250 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	340	Clay and blue shale
340	566	Shale and shells
566	610	Sand
610	970	Shale and sand
970	980	Anhydrite
980	1065	Shale
1065	1305	Sand
1305	1610	Shale
1610	1648	Anhydrite
1648	1651	Shale
1651	2125	Shale and shells
2125	2420	Shale and lime
2420	3855	Lime and shale
3855	4357	Lime
4357	4371	Lime and sand
4371	4420	Lime and shale
4420	4441	Lime and chert
4441		Rotary total depth

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1973
CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.


Don Gardner

Subscribed and sworn to before me this 9th day of August, 1973.

My commission expires:
December 14, 1973


Notary Public