


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 17 Twp. 18 Rge. 24 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE SE
Lease Owner A. Scott Ritchie
Lease Name Stenzel #1 Well No. _____
Office Address Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4/5/78 _____ 19____
Plugging completed 4/10/78 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4367
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	293	none
				4 1/2"	3322'	3322'
					4366'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4290' and ran 3 sacks cement. Shot pipe at 3790', 3589', 3320', pulled 100 joints. Allied plugged well with 20 sacks gel, 70 sacks cement, 6 sacks gel, plug and 70 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of _____)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
MR. R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of April, 1978

My commission expires _____



Margaret Melcher
Notary Public.

15-135-21335-0000

D R I L L E R S L O G

Stenzel #1

CASING RECORD:
288' used 24#
8-5/8" surface
casing.

COMPANY: A. Scott Ritchie
CONTRACTOR: Strata Drilling Company
COMMENCED: June 6, 1977
COMPLETED: June 15, 1977

DESCRIPTION: C SE SE
Section 17-18S-24W
Ness County, Kansas
ELEVATION: 2293' CL

TOTAL DEPTH:
4367'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil and shale	0	305	Ran 288' used 24# 8-5/8" surface casing; set and cemented at 293' with 180 sacks common cement, 2% gel, 3% C.C.; cement circulated. Plug down at 10:15 p.m., June 6, 1977. Ran 4 Drill Stem Tests. Ran 1 electric log.
Shale and sand	305	1415	
Shale	1415	1570	
Anhydrite	1570	1610	
Shale	1610	2330	
Shale and lime	2330	4272	
Lime and sand	4272	4317	
Lime	4317	4327	
Mississippi	4327	4367	

Ran 132 jts. new 4½" casing, set at 4366 with 100 sacks 60-40 pozmix, 10 bbls. preflush brine. Plug down at 10:15 a.m., June 15, 1977.

RECEIVED
STATE OIL AND GAS COMMISSION

MAR 10 1978

STATE OF KANSAS)
)ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Subscribed and sworn to before me this 21st day of June, 1977.

My commission expires: March 28, 1980.

Loneita Barry
Loneita Barry, Notary Public

