

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,486-0000

LEASE NAME Stenzel

WELL NUMBER 1

1320 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 17 TWP 18S RGE 24 17/6/1(W)

COUNTY Ness

Date Well Completed 8/24/90

Plugging Commenced 8/24/90

Plugging Completed 8/24/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS 3004 Broadway avenue, Hays, KS 67601

PHONE# (913) -625-5891 OPERATORS LICENSE NO. 7076

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-24-90 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	251'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mud laden fluid 4360'-1620' 10 sks cement @ 40'
50 sks cement @ 1620' 10 sks cement in mousehole
80 sks cement @ 990 15 sks cement in rathole
40 sks cement @ 279'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, Kansas 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Kyle B. Branum
P. O. Box 506, Russell, KS 67665-0506

GLENDA R. TIFFIN DESCRIBED AND SWORN TO before me this 30th day of August, 1990

NOTARY PUBLIC
STATE OF KANSAS

[Signature]
Glenda R. Tiffin, Notary Public

My Commission Expires: 2-6-92

15-135-23486-0000

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Black Diamond Oil, Inc.
3004 Broadway Avenue
Hays, Kansas 67601

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Stenzel WELL #1

LOCATION: C E/2 E/2 SE
Section 17-18S-24W
Ness County, Kansas

LOGGERS TOTAL DEPTH: 4359'

ROTARY TOTAL DEPTH: 4360'

COMMENCED: 8/18/90

CASING: 8-5/8" @ 251' w/150 sks cement

ELEVATION: 2295' K.B.

COMPLETED: 8/25/90

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Shale	40'	Shale	2355'
Dakota Sand	728'	Lime & Shale	3585'
Red Bed	793'	Lansing-Kansas City	3940'
Cedar Hills	1006'	Pawnee	4080'
Red Bed	1255'	Ft. Scott	4183'
Anhydrite	1592'	Mississippi	4280'
Red Bed	1621'	R.T.D.	4360'


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on August 30, 1990.

My commission expires: February 6, 1992.




Glenda R. Tiffin, Notary Public