


15-095-00013-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Kingman County, Sec. 27 Twp. 29 Rge. 10 (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NE  
Lease Owner Aylward Drilling Company et al  
Lease Name Spade Well No. 1  
Office Address 813 1st Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 29 1956  
Application for plugging filed October 29 1956  
Application for plugging approved October 29 1956  
Plugging commenced October 29 1956  
Plugging completed October 29 1956  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4779 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	259'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 240'; cement plug with 20 sacks of cement from 240' to 200'; heavy mud to 35'; cement plug with 10 sacks of cement from 35' to top of surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company  
Address 813 1st Nat'l Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Paul W. Hesse (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse  
813 1st Nat'l Bank Bldg. - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 1956

My commission expires December 11, 1957

Duane Jessup Notary Public

PLUGGING  
FILE SEC 27 T. 29 R. 10 W  
BOOK PAGE 111 LINE 34

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 11-15-56  
PLUGGING DIVISION

SPADE #1

Casing Record:  
8 5/8" - 260'

Company: Aylward Drilling Company  
Contractor: Aylward Drilling Company

Location: SE SE NE 27-29-10W  
Kingman County  
Kansas

Commenced: October 11, 1956  
Completed: October 28, 1956

Elevation: 1735 D.F.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Clay	0	35	Set 8 5/8" pipe at 260' w/185 sx cement
Sand	35	230	
Red Rock	230	258	Geological Tops:
Red Rock & Blue Shale	258	1140	
Salt	1140	1230	Heebner 3536
Gray Shale	1230	1480	Douglas 3607
Shale & Shells	1480	1570	Missouri 3707
Anhydrite	1570	1600	B/Kansas City 4157
Lime & Shale	1600	1795	Des Moines 4170
Ft. Riley	1795	1925	Mississippian 4307
Lime & Shale	1925	2445	Kinderhook 4372
Shale	2445	2685	Viola 4582
Shale & Lime	2685	3017	Simpson 4649
Sandy Lime	3017	3175	Arbuckle 4754
Sandy Lime & Shale	3175	3285	T.J. 4779
Lime & Shale	3285	3317	DST 4309-27 - Open 2 hr.; Wk. stdy. blow Rec. 60' very slightly OCA, 90' Wtry Mud. IBHP 1615 $\frac{1}{2}$ /30 min.; FP 40 $\frac{1}{2}$ - 70 $\frac{1}{2}$ FBHP 1020 $\frac{1}{2}$ /30 min.
Sandy Lime	3317	3437	
Lime & Shale	3437	3623	DST 4584-96 - Open 1 hr. Rec. 14' mud BHP 0
Lime	3623	4033	
Lime & Shale Streaks	4033	4082	Lime 4082 4154 Lime and Shale 4154 4317 Miss. Chert 4317 4327 Miss. 4327 4360 Miss. Lime 4360 4403 Lime & Shale 4403 4484 Shale 4484 4571 Lime 4571 4596 Cherty Lime 4596 4613 Lime 4613 4644 Sand 4644 4676 Sand & Shale 4676 4716 Sandy Shale 4716 4761 Lime 4761 4779 T.D.
Lime	4082	4154	
Lime and Shale	4154	4317	
Miss. Chert	4317	4327	
Miss.	4327	4360	
Miss. Lime	4360	4403	
Lime & Shale	4403	4484	
Shale	4484	4571	
Lime	4571	4596	
Cherty Lime	4596	4613	
Lime	4613	4644	
Sand	4644	4676	
Sand & Shale	4676	4716	
Sandy Shale	4716	4761	
Lime	4761	4779 T.D.	

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

*Aylward*

Subscribed and sworn to before me this 6<sup>TH</sup> of November, 1956.

*Duane Jessup*  
Notary Public

My commission expires December 11, 1957.

**PLUGGING**  
FILE SEC 27 T. 29 R. 10W  
BOOK PAGE 111 LINE 34

RECORDED  
INDEXED  
NOV 29 1956