

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67702

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20394-0000

Lease Name Edsall G

WELL NUMBER 5

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3630 Ft. from S Section Line

3228 Ft. from E Section Line

SEC. 6 TWP. 16S RGE. 42W (E) or (W)

COUNTY Greeley

Date well completed 9/26/85

Plugging Commenced 10/18/99

Plugging completed 10/18/99

LEASE OPERATOR Herman L. Loeb

Address P. O. Box 524 Lawrenceville, IL 62439

Phone (618) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/25/99 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? _____

Producing Formation Morrow Depth to Top 5131' Bottom 5152' T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>0:1</u>	<u>5131'</u>	<u>5152'</u>	<u>8 5/8"</u>	<u>389'</u>	<u>0'</u>
				<u>4 1/2"</u>	<u>5300'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, State the character of same and depth placed, from feet to feet each set. Set CIBP @ 5100', spot 2 sk cement on top. Run cement bond log, no cement above 2000'. Set CIBP @ 2000', perforate @ 1950'. RIH w/ tubing to 1950', pump 125 sk down tubing, lose circulation. Pull tubing to 600', pump 55 sk cement, circulate cement to surface, POH w/ tubing. Hook on to 8 5/8" surface casing, pump 100 sk cement down annulus. Top off 4 1/2" casing w/ 30 sk cement. All cement 60/40 pozmix w/ 6% gel.

Name of Plugging Contractor Mull Drilling License No. 5144

Address P O Box 2758 Wichita, KS 67201-2758

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 28th day of October, 19 99

Donna Carlene Lucas
Notary Public

My commission expires: April 6, 2002

RECEIVED
STATE CORPORATION COMMISSION

11-1-99
NOV - 1 1999

OFFICIAL SEAL
DONNA CARLENE LUCAS
Notary Public, State of Illinois
Commission Expires: 4/6/02

FORM CP-4
K