

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20,400-00-00

LEASE NAME Edsall

WELL NUMBER G-7

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 6 TWP. 16S RGE. 42 ~~W~~(W)

COUNTY Greeley

Date Well Completed 11/22/85

Plugging Commenced 11/22/85

Plugging Completed 11/22/85

TIGHT HOLE

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TXO Production Corp.

ADDRESS 1800 Lincoln Center Bldg.; Denver, CO 80264

PHONE#(303) 861-4246 OPERATORS LICENSE NO. 5171

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.D. 5230'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	tight	0	384	8-5/8"	384	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

The hole was filled w/ 9.1#/gal drilling mud. A 50 sx plug was set @ 2770-2300', a 50 sx plug was set @ 1600-1300', a 40 sx plug was set @ 700' to 400', a 40 sx plug was set @ 385-100', a 10 sx plug was set @ 40' to surface. Circulated the RH & MH w/ 10 sxs of cement. All cement was 60-40 poz-mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell/Schlumberger License No. _____

Address Ulysses, Kansas

STATE OF Colorado COUNTY OF Denver, ss.

Frank D. Tsuru (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank D. Tsuru

(Address) 1800 Lincoln Center Bldg. Denver, Colorado 80264

SUBSCRIBED AND SWORN TO before me this 17 day of January, 19 86

Nada J. Blanson

My Commission Expires: Dec 14, 1986 Notary Public

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1986
3-31-86
CONSERVATION DIVISION
Wichita, Kansas

FEB 24 1986

Form CP-
Revised 08-8

CONSERVATION DIVISION