

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20371-0000

LEASE NAME Edsall

WELL NUMBER G-2

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 6 TWP. 16S RGE. 42 KEY (W)

COUNTY Greeley

Date Well Completed 7/24/85

Plugging Commenced 7/25/85

Plugging Completed 7/25/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TXO Production Corp.

ADDRESS 1800 Lincoln Center Bldg., Denver, CO 80264

PHONE#(303) 861-4246 OPERATORS LICENSE NO. 5171

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes CL

Which KCC/KDHE Joint Office did you notify? District Office #1

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5126 Bottom 5130 T.D. 5270

Show depth and thickness of all water, oil and gas formations.

TIGHT HOLE

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	tite	0	474	8-5/8"	474'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. The hole was filled w/ 9.1 #/cal mud all plugs were 60/40 poz mix cmt. 50 sxs were set from 2770'-2600', 50 sxs from 1350'-1180', 40 sxs from 720'-620', 40 sxs from 480'-380', 10 sxs from 40'- surface. 10 sxs in RH - 10 sxs in MH. Csg cut 3' below GL elevation & buried.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell/Schlumberger License No. _____

Address Ulysses, Kansas

STATE OF Kansas COUNTY OF _____, ss.

Frank D. Tsuru (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank D. Tsuru

(Address) 1800 Lincoln Center Bldg. Denver, Colorado 80264

SUBSCRIBED AND SWORN TO before me this 4 day of September, 19 85

Nada J. Branson
Notary Public

My Commission Expires: _____

RECEIVED
STATE CORPORATION COMMISSION
9-16-85
SEP 16 1985