

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67702

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-071-20384 - 0000

Lease Name Edsall G

WELL NUMBER 3X

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2970 Ft. from S Section Line

2975 Ft. from E Section Line

SEC. 6 TWP. 16S RGE. 42W (E) or (W)

COUNTY Greeley

Date well completed 9/3/85

Plugging Commenced 9/27/99

Plugging completed 9/27/99

LEASE OPERATOR Herman L. Loeb

Address P.O. Box 524 Lawrenceville, IL 62439

Phone (618) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/2/99 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? YES If not, IS well log attached? NO

Producing Formation Morrow Depth to Top 5146' Bottom 5158' T.D. 5280'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>5146'</u>	<u>5158'</u>	<u>8 5/8"</u>	<u>461'</u>	<u>0'</u>
				<u>4 1/2"</u>	<u>5280'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, State the character of same and depth placed, from feet to feet each set
Tubing shot off @ 2433'. RIH w/ tubing & packer, set packer @ 2378'. Pump 100 sk cement w/ 200# of hulls, displace to the packer. POH w/ tubing & packer. Set cast iron bridge plug @ 2000'. Perforate @ 1790' (TOC @ 1840'). Pump 180 sk cement (0' to 1790') down 4 1/2" casing. Hook on to 8 5/8" surface casing, pump 100 sk cement down 4 1/2" x 8 5/8" annulus. Use 60/40 poz mix w/ 6% gel.

Name of Plugging Contractor Mull Drilling License No. 5144

Address P O Box 2758 Wichita, KS 67201-2758

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne


(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 12th day of October, 19 99

Donna Carlene Lucas
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 10-12-99
 OCT 12 1999

My Commission Expires: April 6, 2002



Form CP-4

CONSERVATION DIVISION
 Wichita, Kansas...

2