

RECEIVED

AUG 20 2012

Form CP-4
March 2009

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Type or Print on this Form
Form must be Signed
All blanks must be Filled

WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA

OPERATOR: License #: 7288
 Name: PAUL E. KLOBERDANZ
 Address 1: P.O. BOX 57756
 Address 2: _____
 City: OKLAHOMA CITY State: OK Zip: 73157-7756
 Contact Person: PAUL E. KLOBERDANZ
 Phone: (405) 947-5570

Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)
LAYTON Depth to Top: 1760 Bottom: 1780 T.D. 1952
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 019-21413-00-00
 Spot Description: _____
NE-NE-NE Sec. 15 Twp. 32 S. R. 8 East West
180 Feet from North South Line of Section
330 Feet from East West Line of Section

Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW

County: Chautauque
 Lease Name: MX+O Well #: 6
 Date Well Completed: 10-11-79
 The plugging proposal was approved on: 7-20-12 (Date)
 by: DUANNE SIMS (KCC District Agent's Name)
 Plugging Commenced: 7-17-12
 Plugging Completed: 7-20-12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LAYTON	GAS	SURFACE	7"	102'	NONE
		PRODUCTION	4 1/2"	1951'	800'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1" To 1725 Gel Hole Spotted 5 sks Cement Pulled 1" out
 Shot casing off At 800' Laid out casing Ran 1" To 800' Spotted
 10 sks cement Pulled 1" upto 550' Cemented To Surface With
 110 sks Cement.

Plugging Contractor License #: 32884 Name: Elmores Inc
 Address 1: 776 Hwy 99 Address 2: _____
 City: Sedan State: KS Zip: 67361
 Phone: (620) 249 2519

Name of Party Responsible for Plugging Fees: Paul Kloberdanz
 State of OKLAHOMA County, OKLAHOMA, ss.
PAUL E. KLOBERDANZ Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Paul E Kloberdanz

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials 'JK' in the bottom right corner.