


15-135-20199-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ness County, Sec 34 Twp. 20S Rge. (E) 21 (W)  
Location as "NE/CNW/SW" or footage from lines C SE NW  
Lease Owner Rains & Williamson Oil Co., Inc.  
Lease Name BELTZ Well No. 1  
Office Address 1425 Wichita Plaza - Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-1 19 68  
Application for plugging filed 11-1 19 68  
Application for plugging approved 11-1 19 68  
Plugging commenced 11-1 19 68  
Plugging completed 2:30 AM 11-2 19 68  
Reason for abandonment of well or producing formation No oil or gas found  
in commercial quantities.  
If a producing well is abandoned, date of last production -- 19 --  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4414 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	276'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 600'. Spotted 70 sacks 50-50 Pozmix with 6% gel.  
Mud back to 270', spotted 20 sacks same. Mud back to 40',  
set solid bridge and capped with 10 sacks, 2 sacks in rat hole.


RECEIVED  
STATE CORPORATION COMMISSION  
NOV 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rains & Williamson Oil Co., Inc.  
Address 1425 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wilson Rains (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains  
1425 Wichita Plaza - Wichita, Kansas  
(Address)



SUBSCRIBED AND SWORN TO before me this 7 day of November, 19 68

My commission expires June 30, 1971 Sherry Gish Notary Public.

15-135-20199-0000

ROTARY DRILLING LOG

Operator: Rains & Williamson  
Oil Co., Inc.  
BELTZ #1  
C SE NW 34-20S-21W  
Ness County, Kansas

Contractor: Rains & Williamson  
Oil Co., Inc.  
Commenced: 10-23-68  
Completed: 11-1-68

Casing: 8-5/8" @ 276' w/170 sx.

Formations

Surface Clay and Rock	45'
Shale	758'
Blaine Anhy.	767'
Shale	850'
Sand	1065'
Shale and Red Bed	1405'
Anhydrite	1441'
Shale	1921'
Shale and Lime	2260'
Lime and Shale	2552'
Lime	2785'
Shale and Lime	3780'
Lime	4414'
Rotary Total Depth (D&A)	4414'

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains  
Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 7th day of November, 1968.

Sherry Gish  
Sherry Gish Notary Public

My Commission Expires:  
June 30, 1971

