

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-05742-00-02
Spot: NWNENW Sec/Twnshp/Rge: 31-19S-1W
4786 feet from S Section Line, 3451 feet from E Section Line
Lease Name: LAGREE Well #: 2
County: MCPHERSON Total Vertical Depth: 3950 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	6.625	2932		
PROD	5.5	3575		
SURF	12.5	1038		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2012 9:00 AM
Plug Co. License No.: _____ Plug Co. Name: _____
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS, AS PER THEIR RECOMMENDATIONS

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL
Date/Time Plugging Completed: 06/23/2012 10:00 AM KCC Agent: HUNTER CLARK

Actual Plugging Report:

Perfs:

6-22-12 RAN TUBING DOWN TO 3950' SET SAND WITH DUMP BAILER, AND A 25 SX PLUG 60/40%, 5% GEL INSIDE 4.5". THEN PULLED UP TO 375' PUMPED 110 SX PLUG OF 60/40%, 5% GEL AND 3 BAGS OF HULLS IN THE 16". 130 SX PLUG OF 60/40%, 5% GEL AND 3 BAGS OF HULLS INSIDE THE 7". 115 SX INSIDE THE 4.5" OF 60/40%, 5% GEL AND 3 BAGS OF HULLS. RAN THE SWAB LINE DOWN TAGGED AT 375' INSIDE 16", AND 300 INSIDE 7". PERFORATED WELL AT 265' 4 SHOTS PER FOOT. PUMPED 340 SX OF 60/40% DOWN HOLE THE 4.5". RAN OUT OF CEMENT WILL RETURN ON SAT. TO FINISH THE WELL. 6-23-12 TAGGED CEMENT 80' SINDIE 4.5" AND 75' INSIDE 16" PUMPED A TOTAL OF 110 SX OF 60/40% CIRCULATED TO TOP, TO COMPLETE THE PLUGGING OF THE WELL.


Remarks: CEMENT TICKET #37691 GRESSEL

Plugged through: TBG

RECEIVED
JUL 10 2012
KCC WICHITA

District: 02

Signed



(TECHNICIAN)