

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20479-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 13-19S-2E
4968 feet from S Section Line, 2075 feet from E Section Line
Lease Name: REMPEL Well #: 5
County: MARION Total Vertical Depth: 3000 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2900		125 SX
SURF	8.625	223		60 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2012 3:00 PM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: BARRY CONSIDINE Company: _____ Phone: (620) 755-2744

Proposed
Plugging
Method:

AS PER KCC RULES AND REGULATIONS, AS PER THEIR RECOMMENDATIONS.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 06/20/2012 5:00 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

Perfs:

RAN TO TD AND SET 25 SX AT THE BOTTOM OF THE WELL. THEN RAN DOWN TO 2400' SANDED OFF AND SET A 5 SX PLUG WITH 60/40% MIX. RAN SAND LINE HIT PLUG AT 2350'. PERF AT 275' INSIDE CASING, RAN TUBING DOWN TO 275' CIRCULATED WATER, THEN USED 135 SX OF 60/40% AND 3 BAGS OF HULLS CIRCULATED TO SURFACE.

Remarks: GRESSEL CEMENT TICKET #37959


Plugged through: TBG

RECEIVED
JUL 10 2012

KCC WICHITA

District: 02

Signed



(TECHNICIAN)