

6 030987

10-27-87

API NUMBER 15- 109-20,355-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SE SE, SEC. 20, T 12 S, R 33 (W) 8  
330 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Bertrand Well # 2

Operator: A. L. Abercrombie  
Name & Address: 801 Union Center Bldg.  
Wichita, Kansas 67202

County Logan 154.70

Well Total Depth 4760 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B. J. Titan License Number \_\_\_\_\_

Address Oakley, Kansas

Company to plug at: Hour: PM Day: 27 Month: Oct. Year: 19 87

Plugging proposal received from Bill Sowles

(company name) A. L. Abercrombie (phone) \_\_\_\_\_

were: 8 5/8" set at 345' w/200 sks cwc 4 1/2" set at 4757' w/225 sks DV 2600' cwc.

Perf 4319' - 4323'. Order 200 sks Thrifty Mix 65/35 Poz 10% Gel 2% Dicl

B. J. Titan Cement Blend 5 sks Hulls. Newman Water Truck.

Elev. 3148' GL

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00PM Day: 27 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT

Squeeze 4 1/2" casing w/200 sks Cement Blend w/3 sks Hulls mixed in to Max Psi 1300#. Close in Psi 1200#. Backside had cement down 50' filled with cement to base of cellar. Plug complete.

11-30-87

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 12-4-87

INV. NO. 19082