

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-109-20,258 ✓

SE, Sec. 17, T 12 S, R 33 W/E

330 feet from N(S) section line

990 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Math H.H. Well # 1

Operator: Slawson, Donald C. Oil Producer
Name & Address 200 Douglas Bldg. Wichita, Ks. 67202

County Logan

Well Total Depth 4800 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 328'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Co. Inc. License Number 240

Address 200 Douglas Bldg. Wichita, Ks. 67202

Company to plug at: Hour: 4:00 PM Day: 6 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Jimmie Loftis

(company name) Slawson Drilling Co. Inc. (phone) 316-225-9636

were: Orders out 160 sacks 50 per cent - 4% cel. - 3% cal. cl. + 8 5/8" plug.

Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 2630' w/ 20 sacks

2nd plug C 1500' w/ 80 sacks, 3rd plug C 350' w/ 40 sacks, 4th plug C 40'

solid bridge of hulls + plug w/ 10 sacks. Circulate 10 sacks in rat hole.

Signed Gilbert R. Schulz
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:15 PM Day: 6 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" S.P. 328' w/ 225 sacks common - 2% cel. - 3% cal. cl.

Ordered 160 sacks 50 per cent - 4% cel. - 3% cal. cl. + 8 5/8" plug. Spot w/ drill stem

w/ heavy mud between all plugs. 1st plug C 2630' w/ 20 sacks, 2nd plug C 1500' w/

80 sacks, 3rd plug C 350' w/ 40 sacks, 4th plug - solid bridge of hulls + plug

C 40' w/ 10 sacks. Circulate 10 sacks in rat hole.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
10-19-82
OCT 19 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Gilbert R. Schulz
(TECHNICIAN)

DATE 11-18-82
REV. NO. 1643-W

D