

To: 6 041324  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-23  
API NUMBER 15-109-20508-0000  
100' SE of SW SW SW, SEC. 17, T 12 S, R 33 (W/E)

330 feet from S section line  
4850 feet from E section line

Lease Name Clark Well # A-3

County Logan 155.02

Well Total Depth 4770' feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 351'w/200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing License Number \_\_\_\_\_

Address Chase, Kansas

Company to plug at: Hour: 8:00 A.M. Day: 23 Month: 8 Year: 19 91

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 4 1/2" casing set at 4769' w/225 sks. cement. Perfs. at 4286' to 4684'.

Shot anhy. at 2600'. Shot base dakota at 1450'. Plug bottom with sand to

4120' and 4 sks. cement. Ordered 250 sks. 65/35 poz. - 10% gel w/1/2 lb. flocele

plus 300# hulls.

Plugging Proposal Received by Dennis L. HAMEL (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 3:00P.M. Day: 23 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT Shot casing @ 2600' and pumped 50 sks. cement disp. cement

w/12 bbls. gel. mud to 1450'. Shot casing at 1450' and pumped 100 sks. cement disp.

cement with gel. to 600'. Pulled casing to 400' and circulated cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 05 1991

9-5-91

Remarks: \_\_\_\_\_ (If additional description is necessary, use BACK of this form.)

INVOICED  
Do not XXXXXXXX reserve this plugging.

DATE 9-12-91

INV. NO. 33101

Signed Dennis L. Hamel (TECHNICIAN)