

6 030693

API NUMBER 15-109-20,175-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

565' FUL
725' FEL
4715' FSL
NE/C. SEC. 2, T. 14 S, R. 33 (W) 1/4
feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181
Operator: DONALD C. SLAWSON
Name & Address 200 DOUGLAS BLDG.
WICHITA, KANSAS
67202

Lease Name HOBBLE Well # D 1
County LOGAN 149.83
Well Total Depth 4610' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 330'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050
Address CHASE KANSAS

Company to plug at: Hour: AM Day: 7 Month: 3 Year: 19 86

Plugging proposal received from BILL FULLS
(company name) KELSO CASING (phone) _____

were: 8 5/8 @ 330' w/250sx. 4 1/2 @ 4140 w/250sx. PERF 4010-15'
PBTD 4090' ORDER SAND-COM. CNT. SHOOT & STRIP PIPE
ORDER 180 SX. 60/40 POL GEL 3 1/2" 40 SX. GEL. 4 SX. HULLS 8 5/8 W.P.
HALLIBURTON CNT. CO. WELLBROCK WATER TRUCK.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12: PM Day: 7 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 4950' SPOT 4SX. COM. CNT. ON SAND W/BRAILER.
SHOT & RECOVERED 2500' OF 4 1/2"
MIX. & Pump DOWN 8 5/8 3SX. HULLS 25 SX. GEL. 100 SX. CNT + 1 SX. HULLS
15 SX. GEL. 8 5/8 W.P. 80 SX. CNT MIX. MAX. PSI 500* CLOSE IN 250*
PLUG. COMPLETE

RECEIVED
STATE CORPORATION COMMISSION
3-24-86
MAR 24 1986

Remarks: Additional description is necessary, use BACK of this form
I (did/did not) observe this plugging.

INVOICED

DATE 13118
INV. NO. 13118

Signed Carl Goodnow
(TECHNICIAN)