

4-032108

11-8

20107 00-01

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-199-21-017-0000

SW SW \_\_\_\_\_ /4 SEC. 31 , 14 , 42 W  
660 feet from S section line  
4620 feet from E section line

Operator license# 6417

Lease: Arapahoe Unit Well # 117

Operator: Union Pacific Resources

County: Wallace

Address: 15562 Highway 385  
Cheyenne Wells, CO 80810

Well total depth 5300 <sup>172.25</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 681 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cement Company License# \_\_\_\_\_

Address: Oakley, Kansas 67748

Company to plug at: Hour: P.M. Day: 8 Month: November Year: 1995

Plugging proposal received from: Larry Bryant

Company: Union Pacific Resources Phone: \_\_\_\_\_

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls - 10 sxs. gel.

Stamp: RECEIVED NOV 29 1995

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 1:30 P.M., Day: 8, Month: November, Year: 1995

Actual plugging report: 8 5/8" set at 681' cwc with 150 sxs. 4 1/2" set at 5299' with 150sxs. PBTD 5285'. Port collar at 1997' w/350 sxs lite. Prod. perf. 5183' - 5195'. CIBP at 5150' w/2 sxs common cement. Ran tubing to 5138' - displaced 50 sxs cement blend with 300# hulls. Pulled tubing to 4438' - displaced 25 bbls gel. Pulled tubing to 2800' - circulated to surface with 100 sxs cement blend. Laid down tubing - topped off 4 1/2" with 20 sxs cement blend. Squeezed 8 5/8" with 75 sxs cement blend. Plug complete.

Remarks: GL 3926' - Anhy. 2880' - Top DK 1520' - Top Blaine 2347'.

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES \_\_\_\_\_ NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did X / did not [ ] observe the plugging.

Carl Goodrow  
(agent)  
Form CP-2/3

INVOICED  
DATE 12-4 1995

INV. NO. 44188 11-8 JAN 17 1996