

4-17-88

P

To: 6 270674  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,150.0000  
SW NW SW SEC. 31, T 14, S, R 42 W1.  
1650 feet from S section line  
4820 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171  
Operator: TXO Production Corp  
Name & Address: 155 N Market #1000  
Wichita, Ks. 67202  
Cory West

Lease Name Hibbert Well # C 2  
County Wallace 172.25  
Well Total Depth 5300 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 689

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 N Water #300 Wichita, Ks. 67202

Company to plug at: Hour: 11:15PM Day: 17 Month: April Year: 19 88

Plugging proposal received from Gerald Veatch

(company name) TXO Production Corp (phone) \_\_\_\_\_

were: 8 5/8" 689' S.P. cwc w/525 sks cement. Class A and light cement (By Allied).

Miss Well - Elev. 3900' - Anhy 2831'. No circulation problems. Mud conditions 45 vis - 8.9lb. Weight 9. Water Loss. Proposal 225 sks 60/40 Poz 2% Gel 3% CaCl. Spot with drill stem, circulate, heavy mud between all plugs. 25 sks at 2840'; 100 sks at 1950'; 25 sks at 720'; 40 sks at 240'; 10 sks at 40' 15 sks in rat hole. Circulate 10 sks mouse hole (circulate) Cemented by Plugging Proposal Received by Marion J. Schmidt Allied Cement. (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:15PM Day: 17 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Poz 6% Gel 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem, circulated, mud between all plugs. 1st plug at 2840' w/25 sks cement; 2nd plug at 1950' w/100 sks cement; 3rd plug at 720' w/25 sks cement; 4th plug at 240' w/40 sks cement. 5th plug 10 sks at 40'. 15 sks in rat hole (circulate) 10 sks mouse hole. Circulate. Cemented by Allied.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby certify that I have observed this plugging.

DATE 7-8-88

INV. NO. 21256

Signed Marion J. Schmidt (TECHNICIAN)

AUG 3 1988 SEP 12 1988