

4-020117

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

10-16

API number: 15-109-20,635-0000

SE NE NE /4 SEC. 06, 13 S, 33 W  
4290 feet from S section line  
330 feet from E section line

Operator license# 05135

Lease: Nau Well # 2

Operator: John O. Farmer, Inc.  
Address: P.O. Box 352  
Russell, Kansas 67665

County: Logan 152.42  
Well total depth 4690 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Abercrombie, RTD, Inc. License# 30684

Address: 150 N. Main, Suite 801, Wichita KS 67202

Company to plug at: Hour: Day: 16 Month: October Year: 1996

Plugging proposal received from: Tony Martin

Company: Abercrombie, RTD, Inc. Phone: 316 262 1841

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2530 feet with 25 sacks	Rat hole: 15 sacks
2nd plug @ 1460 feet with 100 sacks	
3rd plug @ 300 feet with 40 sacks	
4th plug @ 40 feet with 10 sacks	

10-28-96

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 6:00 PM, Day: 16, Month: October, Year: 1996

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job.

Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES, CALC X, NO  
Plugged through TUBING, CASING X. Elevation: 3055 GL

Anhy.plug: YES X NO  
Dakota plug: YES X NO

I did not observe the plugging.

Ken Kuhn (agent)

Form CP-2/3

INVOICED  
DATE 10-28-96  
INV. NO. 46821