

4- 020088

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-24

API number: 15-109-20,606-0000

SE SE NE /4 SEC. 06, 13 S, 33 W
2310 feet from S section line
330 feet from E section line

Operator license# 05135

Lease: NAU Well # 1

Operator: John O. Farmer, Inc.
Address: P.O. Box 352
Russell, Kansas 67665

County: Logan 151.26
Well total depth 4654 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 257 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Mallard JV, Inc. License# 04958

Address: 2080 East Kansas Avenue, P.O. Box 905, McPherson, KS 67460

Company to plug at: Hour: Day: 24 Month: December Year: 1995

Plugging proposal received from: Carol

Company: Mallard JV, Inc. Phone: 316 241 4640

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2540 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 1440 feet with 100 sacks Mouse hole: 10 sacks
3rd plug @ 310 feet with 40 sacks
4th plug @ 40 feet with 10 sacks

STATE OF KANSAS
DEC 23 1995
12-29-95
WICHITA, KANSAS

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 7:00 AM, Day: 24, Month: December, Year: 1995

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Halliburton, Inc. performed the cement job.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC X, NO
Plugged through TUBING, CASING X. Elevation: 3044 GL

I did (did not) observe the plugging.

Ken Kuhn (agent)

Form CP-2/3

INVOICED

DATE 1-8-96
INV. NO. 44438

TD