

1080273

TO: STATE CORPORATION COMMISSION

API NUMBER 15-071-20,394-0000
NE SE NW SEC. 6, T 16 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2052 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME EDSALL G WELL # 5

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY 172.25

OPERATOR LICENSE # 3273

WELL TOTAL DEPTH 5300 FEET

OPERATOR: HERMAN L. LOEB

PRODUCTION CSG: SIZE 4 1/2" @ 5300' WITH 175 SX

NAME AND PO BOX 524

SURFACE CASING: SIZE 8 5/8" @ 389' WITH 200 SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MULL DRILLING COMPANY INC LICENSE NUMBER 5144

ADDRESS PO BOX 2758 WICHITA, KS 67201-2758

COMPANY TO PLUG AT: HOUR: 9:20 AM DAY: 18 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM M.L. COX

(COMPANY NAME) MULL DRILLING COMPANY INC. (PHONE) 316-264-6366

WERE: PERFS AT 5131-52 DV @ 2774' WITH 350 SX LITE.

SET CIBP @ 5100' WITH 2 SX CEMENT. SET CIBP @ 2000' AND PERFORATED AT 1950'. RUN TUBING IN HOLE TO 1980'. PUMP 125 SX CEMENT. PULLED TUBING TO 600' PUMPED 55 SX CEMENT. PULL TUBING OUT OF HOLE. TOP OFF WITH 30 SX CEMENT. PUMP DOWN 8 5/8" X 4 1/2" ANNULUS 100 SX CEMENT. SHUT IN AT 50#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00 AM DAY: 18 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT PEAK WIRELINE SET CIBP AT 5100' WITH 2 SX CEMENT. SET CIBP AT 2000' AND PERFORATED AT 1950'. MULL DRILLING RAN TUBING IN HOLE TO 1980', ALLIED PUMPED 125 SX CEMENT. PULLED TUBING TO 600' PUMPED 55 SX CEMENT, PULL TUBING OUT OF HOLE. TOPPED OFF WITH 30 SX CEMENT. PUMPED DOWN 8 5/8" x 4 1/2" ANNULUS 100 SX CEMENT. SHUT IN AT 50#

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)
I (DID) OBSERVE THIS PLUGGING.

INVOICED

SIGNED

Kevin J. Strube
(TECHNICIAN)

10-22-99
FORM CP-2/3

DATE 10-29-99

NO. 60772

R