

1 030499

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,385-0000

NE NW SE , SEC. 6 , T 16 S, R 42   
2310 feet from S section line  
1850 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4034

Lease Name Cheek Well # 6

Operator: Remuda Corporation

County Greeley 172.25  
(Mississippi)

Name & Address 490 North 31st, Suite 308

Well Total Depth 5300 feet

Billings, MT 59101

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 471

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 28 Month: August Year: 1985

Plugging proposal received from Terry McRae

(company name) Murfin (phone) 316-267-3241

Elevation 3902 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2779-2811

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' out of the base of the surface pipe with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx and 7th plug to circulate mouse hole with 10 sx

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 5:15 am Day: 28 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 2800' with 50 sx cement, 2nd plug at 1700' with 80  
sx cement, 3rd plug at 500' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 9-6-85

INV. NO. 9894

RECEIVED Steve Durrant  
STATE CORPORATION COMMISSION (TECHNICIAN)  
9-3-85  
SEP 3 1985