

1 030636

API NUMBER 15- 071-20,410-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

App SW NW SW, SEC. 6, T 16 S, R 42 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4034

Operator: Remuda Corporation
Name & Address: P. O. Box 7127
Billings, MT 59103-7127

1500 feet from S section line

4710 feet from E section line

Lease Name Cheek Well # 8

County Greeley 182.00

Well Total Depth 5600 Harrison Shale feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 467

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 29 Month: December Year: 19 85

Plugging proposal received from Bill Ryder

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2905 GL
Elevation 2756-95'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with
10 sx cement Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 am Day: 29 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2795' with 50 sx cement, 2nd plug at 1850' with 80

cement, 3rd plug at 498' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

JAN 07 1986

11877

12-29

JAN 6 1986
1-6-86
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Durrant
(TECHNICIAN)