

1 030476

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,371-0000

SW SE NW, SEC. 6, T 16 S, R 42 W/E

2970 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Edsall "G" Well # 2

Operator: TXO Production Corp.

County Greeley 171.28

Name & Address 1800 Lincoln Center Building

Well Total Depth 5270 feet

Denver, CO 80264

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 474

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 25 Month: July Year: 19 85

Plugging proposal received from Frank Tsuru

(company name) TXO (phone) 303-861-4246

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2770
Elevation 3895

1st plug at 2770' with 50 sx cement

2nd plug at 1350' with 50 sx cement

3rd plug at 720' with 40 sx cement

4th plug at 480' with 40 sx cement

5th plug solid bridge hulls - plug at 40' Plugging Proposal Received by Steve Durrant
cement to surface with 10 sx cement (TECHNICIAN)

7th plug to circulate rat hole with 5 sx cement, 8th plug fill mouse hole with 5 sx cement
Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 3:15 pm Day: 25 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2770' with 50 sx cement, 2nd plug at 1350' with 50 sx cement, 3rd plug at 720' with 40 sx cement, 4th plug at 480' with 40 sx cement, 5th & 6th

plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 7th

plug to circulate rat hole with 5 sx cement, 8th plug to circulate mouse hole with

5 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE AUG 07 1985

Signed Steve Durrant (TECHNICIAN)
AUG 2 1985
8-2-85

INV. NO. 9423

AUG 7 1985

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84