

1080269

TO: STATE CORPORATION COMMISSION

9-27

API NUMBER 15-071-20,384 - 0000
SE SE NW SEC. 6, T 16 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 2235 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2058 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME EDSALL G WELL # 3X

TECHNICIAN'S PLUGGING REPORT COUNTY GREELEY

OPERATOR LICENSE # 3273 WELL TOTAL DEPTH 5280 FEET

OPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 4 1/2" @ 5280' WITH 175 SX

NAME AND ADDRESS PO BOX 524 SURFACE CASING: SIZE 8 5/8" @ 461' WITH 300 SX

ADDRESS LAWRENCEVILLE, IL 62439

INVOICED
10-26-99
D/A

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL DATE

OTHER WELL AS HEREINAFTER INDICATED INV. NO. 60746

PLUGGING CONTRACTOR MULL DRILLING COMPANY INC. LICENSE NUMBER 5144

ADDRESS PO BOX 2758 WICHITA, KS 67201-2758

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 27 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM M.L. COX

(COMPANY NAME) MULL DRILLING (PHONE) 316-264-6366

WERE: PERFS AT 5146-58 TUBING IN HOLE SHOT OFF AT 2433'. (DV @ 2842' WITH 250 SX LITE)
RAN TUBING & PACKER TO 2390'. PUMP 100 SX 60/40 6% 3% CC WITH 200# HULLS. PRESSURED UP
TO 100# PULLED TUBING & PACKER. SET CIBP @ 2000' 7 PERFORATED AT 1790'. BOND LOG SHOWS
CEMENT AT 1840'. PUMP DOWN 4 1/2" AND GOT INJECTION RATE 3 BPM 500#. PUMP 180 SX CEMENT AND
SHUT IN. PUMP DOWN 8 5/8" X 4 1/2" ANNULUS 100 SX. MAXIMUM PSI 500#. SHUT IN 100#. TOP OFF WITH
4 1/2" CASING WITH 25 SX CEMENT. HOLE STAYED LOADED.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 6:30 PM DAY: 27 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT RAN TUBING & PACKER TO 2390'. ALLIED PUMPED 100 SX 60/40 6% & 3% CC
WITH 200# HULLS. PRESSURED UP TO 100# PULLED TUBING & PACKER. PEAK WIRELINE SET CIBP @
2000' & PERFORATED AT 1790'. BOND LOG SHOWS CEMENT AT 1840' ALLIED PUMPED DOWN 4 1/2" AND GOT
INJECTION RATE. 3 BPM 500#. PUMPED CEMENT 60/40 6% 180 SX SHUT IN. PUMPED DOWN 8 5/8" X 4 1/2"
ANNULUS 100 SX CEMENT. MAXIMUM PSI 500#, SHUT IN AT 100#. TOPPED OFF WITH 4 1/2" CASING WITH
25 SX CEMENT. HOLE STAYED LOADED.

RECEIVED
STATE CORPORATION COMMISSION
10-13-99
OCT 15 1999

REMARKS: USED 60/40 6% W/3% CC IN BOTTOM PLUG 60/40 6% TOP PLUG BY ALLIED. NO CASING RECOVERED
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)
I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin P. Strube CONSERVATION DIVISION
(TECHNICIAN) FORM CP-12/93