

1 080604

MAR 19 1987

136

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,436 - 0000

C SE SE, SEC. 27, T 16 S, R 42

520 feet from S section line

520 feet from E section line

Lease Name Young Well # 1

County Greeley 170.63

Well Total Depth 5250 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 313

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 506, Russell, KS 67665-0506

Company to plug at: Hour: 4:30 a.m. Day: 19 Month: 3 Year: 19 87

Plugging proposal received from Hap Halfhill

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3832' KB
Anhydrite 2683-2720'

1st plug at 2700' with 50 sx cement, 2nd plug at 1980' with 100 sx cement,

3rd plug at 340' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by J.H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7 a.m. Day: 19 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2728' with 50 sx cement,

2nd plug at 1980' with 100 sx cement,

3rd plug at 340' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 3-27-87

INV. NO. 16442

Signed J.A. Metz (TECHNICIAN)

MAR 26 1987
3-26-87
FORM CP-2/3
Rev. 01-84