

2011

To: 1 070988  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,550-0000

SW SW NW, SEC. 27, T 16 S, R 42 W/E

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152

Lease Name Young Well # 1-27

Operator: Lee Banks

County Greeley

Name & Address 200 W. Douglas, Suite 550

Well Total Depth 5250 170.62 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Suite 330, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 19 Month: 10 Year: 19 91

Plugging proposal received from Ed McKenna

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2690-2721'

1st plug at 2720' with 50 sx cement, 2nd plug at 1800' with 80 sx cement,

3rd plug at 400' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7 p.m. Day: 19 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2720' with 50 sx cement,

2nd plug at 1800' with 80 sx cement,

3rd plug at 400' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 24 1991  
10-24-91  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 11-13-91

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 33691