

To: 1 120730  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-6 API NUMBER 15-071-~~20571~~ 20571-0054  
NW NW NE, SEC. 27, T. 16 S, R. 42 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3581  
Operator: Red Oak Energy, Inc.  
Name & Address: 200 W. Douglas, Suite 510  
Wichita, KS 67202

4950 feet from S section line  
2310 feet from E section line  
Lease Name Young #2-27 Well # 2  
County Greeley 169.32  
Well Total Depth 5210 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 13 3/8 feet 290

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling, Inc. License Number 30606  
Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 6 Month: 9 Year: 19 92  
Plugging proposal received from Ed McKenna

(company name) Murfin Drilling, Inc. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at 2730' with 50 sx cement, 2nd plug at 1370' with 50 sx cement,  
3rd plug at 690' with 50 sx cement, 4th plug at 330' with 85 sx cement,  
5th plug at 40' with 20 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 2 p.m. Day: 6 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2730' with 50 sx cement,  
2nd plug at 1370' with 50 sx cement, 3rd plug at 690' with 50 sx cement,  
4th plug at 330' with 85 sx cement, 5th plug at 40' with 20 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED  
DATE 10-26-92  
NO: 36580

Signed Duane Rankin (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 9 1992  
CONSERVATION DIVISION  
Wichita, Kansas