

3021734

15-001-01093-0000

TO: API NUMBER 15- CONTROL #20000608-002

STATE CORPORATION COMMISSION SE, SEC. 7, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 82 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1289 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MATHIAS/TUCKER WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY ALLEN

OPERATOR LICENSE # 101 WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING SURFACE CASING: SIZE 8" FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR K.W. WELL SERVICE LICENSE NUMBER 30670

ADDRESS 318 N. FOREST, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 11:30AM DAY: 28 MONTH: 12 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED

IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE

FULL OF CEMENT INSIDE AND OUTSIDE THE 2" CASING.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 3:30PM DAY: 28 MONTH: 12 YEAR: 99

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2" CASING TO 780'. CEMENT WAS PUMPED

INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE

WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 550'. CEMENT WAS PUMPED

INTO THE 1" PIPE UNTIL CEMENT CIRCULATE FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE

WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. CEMENT WAS PUMPED

BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

RECEIVED STATE CORPORATION COMMISSION

REMARKS: (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

JAN 13 2000

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel CONSERVATION DIVISION Wichita, Kansas (TECHNICIAN) FORM CP-2/3

(Handwritten signature/initials)