

3021733

15-001-01094-0000

TO: API NUMBER 15- CONTROL #20000008-003

STATE CORPORATION COMMISSION SE, SEC. 7, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 281 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1136 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MATHIAS/TUCKER WELL # 3

TECHNICIAN'S PLUGGING REPORT COUNTY ALLEN

OPERATOR LICENSE # 101 WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS PRODUCTION CSG: SIZE \_\_\_\_\_ FEET \_\_\_\_\_

NAME AND FEE FUND PLUGGING SURFACE CASING: SIZE 8" FEET N/A

ADDRESS \_\_\_\_\_

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR K.W. WELL SERVICE LICENSE NUMBER 30670

ADDRESS 318 N. FOREST, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 28 MONTH: 12 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE 2" AND 8" ANNULUS WAS OBSTRUCTED NEAR SURFACE. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 2" CASING 2 TIMES AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART X NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 11:30AM DAY: 28 MONTH: 12 YEAR: 99

ACTUAL PLUGGING REPORT AS PER INSTRUCTION, THE 2" CASING WAS PERFORATED AT 200' AND AT 500'. 1" PIPE WAS WASHED INTO THE 2" CASING TO 775'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM BOTH THE 1" AND 2" ANNULUS AND FROM THE 2" AND 8" ANNULUS AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. CEMENT WAS PUMPED BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

RECEIVED  
STATE CORPORATION COMMISSION

REMARKS: \_\_\_\_\_ (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) JAN 13 2000

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel CONSERVATION DIVISION  
(TECHNICIAN) Wichita, Kansas  
FORM CP-2/3