

3021715

TO:

API NUMBER 15-

CONTROL #20000008-08

STATE CORPORATION COMMISSION

SE , SEC. 7 , T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

2242 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

822 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE MATHIAS/TUCKER WELL # 18

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 101

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 8" FEET

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR KEPLEY WELL SERVICE

LICENSE NUMBER 30670

ADDRESS 318 N. FORREST, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 3:00PM DAY: 29 MONTH: 11 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON TITEL

(COMPANY NAME) KCC (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00PM DAY: 29 MONTH: 11 YEAR: 99

ACTUAL PLUGGING REPORT THE 2" CASING WAS PERFORATED AT 200' AND AT 500'. 1" PIPE WAS RAN INTO THE 2" CASING TO 780'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. CEMENT WAS PUMPED BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3