

3021755

15-001-01106-0000

TO: API NUMBER 15- CONTROL #20000008-031

STATE CORPORATION COMMISSION SE, SEC. 7, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 1279 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 796 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MATHIAS/TUCKER WELL # 31

TECHNICIAN'S PLUGGING REPORT COUNTY ALLEN

OPERATOR LICENSE # 161 WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS PRODUCTION CSG: SIZE _____ FEET _____

NAME AND FEE FUND PLUGGING SURFACE CASING: SIZE 4" FEET N/A

ADDRESS _____

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR KEPLEY WELL SERVICE LICENSE NUMBER 30670

ADDRESS 318 N. FOREST, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 10:00AM DAY: 13 MONTH: 1 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT MAY HAVE BEEN
CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 2" CASING AND TO
CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 13 MONTH: 1 YEAR: 2000

ACTUAL PLUGGING REPORT AS PER INSTRUCTION, THE 2" CASING WAS PERFORATED AT 500' AND
AT 200'. 1" PIPE WAS WASHED INTO THE 2" CASING TO 770'. CEMENT WAS PUMPED INTO THE 1"
PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED.
DISPLACEMENT WAS FILLED FROM SURFACE. CEMENT WAS PUMPED BY CONSOLIDATED INDUSTRIAL
SERVICES, INC.

REMARKS: _____

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel (TECHNICIAN)

STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas
 FORM CP-2/3

27 2000

(Handwritten signature/initials in a circle)