

3021770

15-001-01127-0000

TO:

API NUMBER 15- CONTROL #20000008-020

STATE CORPORATION COMMISSION

SE, SEC. 7, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

245 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

1815 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MATHIAS/TUCKER WELL # 20

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 101

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 8" FEET N/A

ADDRESS

ABANDONED OIL WELL GAS WELL INPUT WELL E-2698 SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR K.W. WELL SERVICE LICENSE NUMBER 30670

ADDRESS 318 N. FOREST, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00AM DAY: 26 MONTH: 1 YEAR: 00

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED

IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE

FULL OF CEMENT INSIDE AND OUTSIDE THE 2" CASING.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 1:00PM DAY: 26 MONTH: 1 YEAR: 2000

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2" CASING TO 725'. CEMENT WAS PUMPED

INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE

WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 625'. CEMENT WAS PUMPED

INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1"

PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. CEMENT WAS PUMPED BY

CONSOLIDATED INDUSTRIAL SERVICES, INC. STATE CORPORATION COMMISSION

REMARKS: THIS WAS WELL #153 ON OLD LEASE MAPS. FEB 14 2000

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (XXX/DID NOT) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3

RECEIVED