

3021783

15-001-01144-00-00

TO: API NUMBER 15- CONTROL #20000008-030

STATE CORPORATION COMMISSION SE, SEC. 7, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 50 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 770 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MATHIAS/TUCKER WELL # 36

TECHNICIAN'S PLUGGING REPORT COUNTY ALLEN

OPERATOR LICENSE # 101 WELL TOTAL DEPTH APPROX. 800 FEET

OPERATOR: STATE OF KANSAS PRODUCTION CSG: SIZE \_\_\_\_\_ FEET \_\_\_\_\_

NAME AND FEE FUND PLUGGING SURFACE CASING: SIZE 8" FEET N/A

ADDRESS \_\_\_\_\_

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL E-2698 SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR KEPLEY WELL SERVICE LICENSE NUMBER 30670

ADDRESS 19245 FORD ROAD, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00AM DAY: 9 MONTH: 2 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE X

OPERATIONS COMPLETED: HOUR: 2:00PM DAY: 9 MONTH: 2 YEAR: 2000

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2" CASING TO 654'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 465'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 7 2000

REMARKS: THIS WAS WELL NO. 164 ON THE OLD LEASE MAP.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (XXX/DID NOT) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel  
(TECHNICIAN) FORM CP-2/3

(R)