

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 5 Twp. 11S Rge. 20 (E)(W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner Veeder Supply & Development Co. et al

Lease Name Fischer (Bear-Nixon) Well No. 1

Office Address Box 201, Cherryvale, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Dec. 17, 1956 19

Application for plugging filed Dec. 17, 1956 19

Application for plugging approved Dec. 17, 1956 19

Plugging commenced Dec. 17, 1956 19

Plugging completed Dec. 17, 1956 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 369 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	229'	cemented w/140 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 220' with 20 sacks cement and 1/2 sack hulls;
mud to 40' with 1/2 sack hulls and 10 sacks cement;
cemented to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply and Development Co.

Address Box 201, Cherryvale, Kansas

STATE OF Kansas COUNTY OF Montgomery ss.

C. H. Woods

(employee of owner or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods

Cherryvale, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of December, 1956

Lois Lawson

My commission expires July 11, 1960

Notary Public.

RECORDED
INDEXED
DEC 21 11 18 AM '56
127
01-02-57

Veeder Supply & Dev'l. Co.

Cherryvale, Kansas

Co. et al

Drilled for Bear-Nixon-Veeder Supply & Development Farm Fischer (Bear-Nixon) No 1 Depth 3694'Contractor Veeder Supply & Development Co. Pipe 229' 8 5/8" csg. cemented w/140 sacksLocation NW/4 NW/4 SE/4 Sec. 5 Twp. 11S Range 20WCommenced 12-7-1956 Completed 12-17-1956 County Ellis State Kansas

Soil, sand, gravel	0	70	70	TOPS:	
Blue shale	70	229	159		
Shale	229	510	281	Arbuckle	3669
Shale sand	510	1005	495		
Sand	1005	1200	195		
Shale, red bed	1200	1516	316		
Anhydrite	1516	1557	41		
Shale shells	1557	2025	468		
Shale lime	2025	2100	75		
Shale lime streaks	2100	2140	40		
Lime shale	2140	2480	340		
Lime	2480	2582	102		
Lime and shale	2582	3145	563		
Lime	3145	3694	549		
T. D.	3694				

Dry and abandoned

AFFIDAVITSTATE OF KANSAS)
Montgomery County) ss

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Fischer (Bear-Nixon) #1 well located in Section 5-11S-20W, Ellis County, Kansas, and that the same is true and correct. Further affiant saith not.


THE VEEDER SUPPLY AND DEVELOPMENT CO.

BY C. H. Woods
C. H. Woods

Subscribed and sworn to before me this 20th day of December, 1956.

Walter Lawson
Notary Public

My commission expires July 11, 1960.

RECORDED
STATE COURTCONSERVED
Wichita, Kansas