


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 5 Twp. 11 Rge. (E) 20 (W)
Location as "NE/CNW&SW" or footage from lines NE/NW/NE
Lease Owner Franco Central Oil Company
Lease Name Fischer Well No. 1
Office Address Fourth Nat'l. Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-1-1956
Application for plugging filed 7-1-1956
Application for plugging approved 7-1-1956
Plugging commenced 7-1-1956
Plugging completed 7-1-1956
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3750 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	254'	=0=

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 254' with heavy mud. Set bottom plug with 1/2 sack hulls and 15 sacks cement. Filled with heavy mud to 40'. Set top plug cement with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. Fred Hambricht (employee of ~~owner~~ operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambricht
(Address) _____

SUBSCRIBED AND SWORN TO before me this 6th day of July, 1956

My commission expires August 20, 1956
Arthur R. Derrington
(Arthur R. Derrington) Notary Public.

PLUGGING
FILE SEC. 5 T. 11 R. 20W
BOOK PAGE 77 LINE 41

7-11-56

WELL LOG

15-051-00954-0000

COMPANY Franco Central Oil Company

SEC. 5 T. 11 R. 20

FARM Fischer

NO. 1

LOC. NE/NW/NE

TOTAL DEPTH 3750'

COMM. 6-22-56


COMP. 7-1-56

COUNTY Ellis KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20	10
15	8 5/8" - 2541'
12	6
13	5

ELEVATION 2107 RB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Geologic Tops:

Topeka	3175
Heebner	3360
Lansing	3399
Base Kansas City	3640
Cherty Conglomerate	3674
Arbuckle	3717

0 - 15	Sand, gravel
15 - 125	Blue shale
125 - 1560	Shale and shells
1560 - 1600	Anhydrite
1600 - 2385	Shale and shells
2385 - 3295	Shale and lime
3295 - 3674	Lime
3674 - 3745	Cherty Conglomerate
3745 - 3750	Lime
3750	T. D.

PLUGGING
 FILE SEC. 5 T. 11 R. 20 W.
 BOOK PAGE 77 LINE 41

State of KANSAS
 County of SEDGWICK

I, J. Fred Hambricht of the Lewis Drilling Company upon oath state that the above and foregoing is a true and correct copy of the log of the Fischer #1 well.

Subscribed and sworn to before me this 6th day of July 19 56

My Commission Expires: August 20, 1956

J. Fred Hambricht
 (J. Fred Hambricht)

Arthur R. Derrington
 (Arthur R. Derrington)
NOTARY PUBLIC