

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

15-171-20097-8890
 Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Scott SEC. 25 TWP. 19 RGE. 33 E/W
 Location as in quarters or footage from lines:
C- NW-SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner The Maurice L. Brown Co. Lic. No. 6234
 Lease Name Smith A Well No. #1
 Office Address P.O. Box 11320, Kansas City, MO 64112
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed 10-26-76
 Application for plugging filed 8-1-83
 Plugging commenced 10-4-83
 Plugging completed 10-7-83
 Reason for abandonment of well or producing formation _____

Non commercial Value
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Luthi
 Producing formation Miss. Depth to top 4712 bottom 4718 T.D. 4840
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface				8 5/8"	357'	0'
Production	oil	4712	4718	5 1/2"	4840'	1823'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 2 sks. hulls & 25 sks. cement to 4580' pressured to 750 lbs.
Displace to 1300' w/mud
Pump 35 sks. cement 1300' to 1160'
Displace w/mud
Pump 35 sks. cement 400' to 300'
Put bridge & 10 sks. 40' to 0'
Cut off 8 5/8", 3' below ground level & weld plate on same

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling Service
Lic. # 6497

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
Box F, Sublette, Ks. 67877
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of Oct., 19 83

My Commission expires: 12-6-84

Sondra L. Eves
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 19 1983
 CONSERVATION DIVISION
 Wichita, Kansas



xc: RRP, CAG, LM, DH, EB, File