

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21,495-0000

LEASE NAME Spreier

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 30-A1

1650 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 30 TWP. 16 RGE. 19 (E) or (W)

COUNTY Rush

Date Well Completed 11-9-89

Plugging Commenced 11-9-89

Plugging Completed 11-9-89

LEASE OPERATOR Red Oak Energy, Inc.

ADDRESS 111 West Douglas, Suite 507 Wichita, KS 67202

PHONE# (316) 265-9925 OPERATORS LICENSE NO. 3581

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-08-89 (date)

by Mr. Barlow (KCC District Agent's Name).

Is AC0-1 filed? operator to be filed by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 1355' w/50 sacks 60/40 pozmix 6% gel thru drill pipe
Next Plug: @ 680' w/60 " " " " " " " "
Next Plug: @ 280' w/ 40 " " " " " " " "
Top Plug: @ 40' w/10 sacks cement 15 sacks in Rat Hole
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Duke Drilling Co.

STATE OF Kansas COUNTY OF Barton

Jay Schneider (Employee of Operator) or XXXXXXXXXX of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Jay Schneider

(Address) P.O. Box 823 Great Bend, KS 67530

DOROTHY M. HOGUE
NOTARY PUBLIC
My Commission Expires 5-5-90
I, Jay Schneider, do hereby certify that the above described well was plugged as described on this 14 day of November, 19 89
Dorothy M Hogue
Notary Public

My Commission Expires: 5-5-90

15-165-21495-0000

DRILLER'S WELL LOG

DATE COMMENCED: November 3, 1989
DATE COMPLETED: November 11, 1989

Red Oak Energy, Inc.
SPREIER 30-A1
C S/2 NE SW
Sec. 30, T16S, R19W
Rush County, Ks.

0 - 282' Surface Soil, Shale
282 - 1328' Shale, Sand, Shells
1328 - 1366' Anhydrite
1366 - 3486' Shale & Lime
3486 - 3883' Lime
3883 - 3900' Dolomite
3900' RTD


ELEVATION: 2086 G.L.

Surface Pipe: Set used
8-5/8", 20# pipe #280'
w/160 sacks 60/40 pozmix
2% gel 3% cc.

AFFIDAVIT


STATE OF KANSAS
COUNTY OF BARTON ss

Jay Schneider of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.



Subscribed and sworn to before me this 14 day of November 1989.

Dorothy M. Hague
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1989

CONSERVATION DIVISION
Wichita, Kansas