

15-1165-20378-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rush County. Sec. 28 Twp 6S Rge. XX 19 (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner Pickrell Drilling Company
Lease Name Littler "E" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 10 1971
Application for plugging filed March 10 1971
Application for plugging approved March 10 1971
Plugging commenced March 10 1971
Plugging completed March 10 1971
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3852 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 500' w/70 Sacks, Plug @ 240' w/20 Sacks
Top Plug @ 40' w/10 Sacks Cement

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 16th day of March, 19 71



My commission expires January 19, 1973
Esther Lamone
Notary Public.

15-165-20378-0000
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 3/3/71

Rotary Drilling Completed 3/10/71

LOCATION: Littler "E" No. 1, NE NW Section 28-16S-19W
Rush County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 12 Jts. 8-5/8" surface casing set @ 261' KB. Cemented
w/150 Sacks. Completed 5:00 P.M. Circulated.

No oil string run. D & A, Plugged 3:30 P.M. March 10, 1971

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

100	Post Rock	<u>C.F.S.</u>	
215	Rock - Clay	3360	3785
261	Post Rock - Shale	3425	3795
745	Shale w/sand streaks	3450	3810
930	Sand	3468	3818
1312	Red Beds - Shale	3481	3826
1346	Anhydrite	3525	3852
1625	Shale - Shells	3550	
1975	Shale	3648	
2135	Shale & Lime	3660	
2755	Lime	3685	
2980	Shale & Lime		
3160	Lime - Shale		
3695	Lime		
3775	Lime - Chert		
3818	Cherty Lime	Board <u>S.L.M.</u>	3478.29
3852	Lime - RTD	Strap	3476.96
			<u>1.23 Difference</u>

Slope Tests

2000
2500
3000
3500

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1971
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 16th day of March, 19 71, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts

to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone
Esther Lamone Notary Public