

API NUMBER 15-165-21,505-0000

LEASE NAME Spreier

WELL NUMBER 2-30

330 Ft. from S Section Line

4420 Ft. from E Section Line

SEC. 30 TWP. 16 RGE. 19 (N or W)

COUNTY Rush

Date Well Completed 1-12-90

Plugging Commenced 1-12-90

Plugging Completed 1-12-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Balcron Oil Company

ADDRESS P.O. Box 21017 Billings, Montana 58104

PHONE# (406) 259-7860 OPERATORS LICENSE NO. 3701

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-10-90 (date)

by Mr. Lacy (KCC District Agent's Name).

to be filed

Is ACO-1 filed? by operator If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3930'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 1360' w/50 sacks cement thru drill pipe

Next Plug: @ 700' w/80 sacks " " " " " "

Next Plug: @ 300' w/40 " " " " " " 10 sacks in Mouse Hole

Top Plug: @ 40' w/10 " " " " " " 15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5867

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Balcron Oil Company

STATE OF Kansas COUNTY OF Barton, ss.


RECEIVED
STATE CORPORATION COMMISSION
11-2-3-1990

CONSERVATION DIVISION
Wichita, Kansas

Ervin Neighbors (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530



SUBSCRIBED AND SWORN TO before me this 18 day of Jan., 19 90

Dorothy M. Hague
Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: January 6, 1990
DATE COMPLETED: January 12, 1990

Balceron Oil Company
SPRINKER #2-30
Irregular Section
C S/2 SW SW
Sec. 30, T16S, R19W
Rush County, Ks.

0 - 302' Surface Soil, Clay, Shale
302 - 1329' Sandstone, Shale
1329 - 1364' Anhydrite
1364 - 1965' Red Bud, Shale, Lime
1965 - 2878' Shale & Lime
2878 - 3104' Lime & Shale
3104 - 3559' Shale & Lime
3559 - 3930' Shale & Lime
3930' RED

ELEVATION: 2093 K.B.

Surface Pipe: Set new
8-5/8", 20# pipe @ 300'
w/160 sacks 60/40 posmix
2X gel 3X cc.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 18 day of January 1990.

Dorothy M. Hague
Notary Public



RECEIVED
STATE COMMISSION

JAN 21 1990

CONSERVATION DIVISION
Wichita, Kansas