

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 21 Twp. 18S Rge. 26W E/W
Location as "NE/CNW/SW" or footage from lines
C SE NW


Lease Owner Sanders Oil Company
Lease Name Riebel Well No. 1
Office Address 910 Sutton Place, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed August 19, 1979
Application for plugging filed August 19, 1979
Application for plugging approved August 19, 1979
Plugging commenced August 19, 1979
Plugging completed August 19, 1979
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4690'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	340'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Mud to 1170', 70 sacks cement
- Mud to 335', 20 sacks cement
- Mud to 40', plug, 1/4 sack hulls
- 10 sacks cement, 5 sacks in rat hole

RECEIVED
STATE CORPORATION COMMISSION
SEP - 4 1979

CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Donald E. Hunt (employee of owner) ~~owner/operator~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald E. Hunt
Suite 250, 200 W. Douglas, Wichita, Kansas
(Address)



Subscribed and sworn to before me this 31st day of August, 1979
Dorothy M. Mikish Notary Public.

DRILLERS LOG

#1 RIEBEL
 C SE NW Section 21-18S-26W
 Ness County, Kansas

OPERATOR: SANDERS OIL COMPANY
 910 Sutton Place
 Wichita, Kansas 67202

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.
 Suite 250, 200 West Douglas
 Wichita, Kansas 67202

COMMENCED: August 11, 1979

COMPLETED: August 19, 1979

CASING RECORD: 8-5/8" @ 340' w/250 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	351	Sand & shale
351	1362	Shale & red bed
1362	1375	Blaine
1375	1438	Shale & shells
1438	1695	Sand
1695	1800	Shale
1800	1961	Shale & lime
1961	1990	Anhydrite
1990	2290	Lime & shale
2290	2574	Lime
2574	2810	Lime & shale
2810	2990	Lime
2990	3950	Lime & shale
3950	4690	Lime
		Rotary total depth

RECEIVED
 STATE CORPORATION COMMISSION

SEP - 4 1979

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

Donald E. Hunt
 Donald E. Hunt

Subscribed and sworn to before me this 31st day of August, 1979.

My appointment expires:
 March 1, 1982

Dorothy M. Michalski
 Notary Public

