

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 2 Twp. 19S Rge. 23 E/W
Location as "NE/CNW/SW" or footage from lines

SE NE

Lease Owner Euwer Petroleum Co.
Lease Name Ronald Robinson Well No. #1
Office Address KSB&T Bldg. - Suite 816, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 11-11-82 19
Application for plugging filed 11-11-82 19
Application for plugging approved 11-11-82 19
Plugging commenced 11-11-82 19
Plugging completed 11-11-82 19
Reason for abandonment of well or producing formation

Commercial quantities of oil not found

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation Depth to top Bottom Total Depth of Well 4400'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	524'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 960' w/70 sx.
Plug @ 540' w/40 sx.
Plug @ 40' w/10 sx.
Rat Hole 10 sx.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
I, Wilson Rains, President of Rains & Williamson Oil Co., (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of November, 19 82

Juanita M. Green
Notary Public.

My commission expires 10-4-83



15-135-22317-0000

DRILLER'S LOG

COMPANY: Euwer Petroleum Co.

SEC. 2 T. 19S R. 23W

LOC. SE NE

WELL NAME: Ronald Robinson #1

COUNTY: Ness

RIG NO. #4

TOTAL DEPTH 4400'

ELEVATION

COMMENCED: 11-3-82

COMPLETED: 11-11-82

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 524' w/250 sx. 50/50 poz., 2% gel, 3% cc. and 100 sx. Class A, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Sand & Shale	100
Shale	1380
Shale & Shells	1523
Shale	2150
Shale & Lime	2355
Lime & Shale	4028
Lime	4130
Lime & Shale	4265
Lime	4400
<u>ROTARY TOTAL DEPTH</u>	<u>4400</u>


STATE OF Kansas)
COUNTY OF Sedgwick) SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.
upon oath state that the above and foregoing is a true and correct copy of the log of the
Ronald Robinson #1 well.

Wilson Rains
Wilson Rains

Subscribed and sworn before me this 15 day of November, 1982.

Juanita M. Green
Juanita M. Green



RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1982
CONSERVATION DIVISION
Wichita, Kansas