

15-135-19125-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 5 Twp. 18S Rge. (E) 26 (W)

Location as "NE/CNW/SW" or footage from lines C-SW/4-NW/4

Lease Owner Amerada Petroleum Corporation

Lease Name D.V. Smith Tract 1 Well No. 1

Office Address Box 197, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 7-3- 19 63

Application for plugging filed 10-12- 19 64

Application for plugging approved 10-13- 19 64

Plugging commenced 12 Noon 10-22- 19 64

Plugging completed 2 p.m. 10-22- 19 64

Reason for abandonment of well or producing formation Not Economical to Operate

If a producing well is abandoned, date of last production 10-8- 19 64

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Marmaton Depth to top 4268' Bottom 4403' Total Depth of Well 4540 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Marmaton	Oil-Water	4312'	4320'	4 1/2"	4517'	3313'
				8-5/8"	322'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with Sand from 4356' to 4302', Mixed and Dumped 4 Sacks Cement from 4302' to 4263'.

Filled hole with Heavy Gel Mud from 4263' to 700'

Spotted Cement Plug by Halliburton from 700' to 630' with 20 Sacks Cement Thru 4 1/2" Casing

Filled hole with Heavy Gel Mud from 630' to 300'

Spotted Cement Plug by Halliburton from 300' to 233' With 20 Sacks Cement thru 4 1/2" Casing

Filled hole with Heavy Gel Mud from 233' to 35'

Spotted Cement Plug by Halliburton from 35' to bottom of cellar with 10 Sacks Cement Thru 4 1/2" Casing. Finished at 2:00 p.m. 10-22-64.

RECORDED
STATE CORPORATION COMMISSION

OCT 28 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn and Smith Casing Pulling Company

Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

C.E. Richardson

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 197, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 27th day of October, 19 64

Charles W. Anderson

Notary Public.

My commission expires November 21, 1965


WELL LOG

15-135-19125-000

COMPANY **Adela Petroleum Corp.**
 FARM **D. V. Smith** NO. **One**
 RID. NO. **12**
 TOTAL DEPTH **4540'**
 COMM. **6-10-63** COMP. **6-24-63**
 SHOT OR TREATED
 CONTRACTOR **Wurfin Drilling Company**
 ISSUED

SEC. 5 T. 26 S. R. 26 E.
 LOC. 6/8. NW

COUNTRY **MISSOURI**
KANSAS



CASINO
 20 10
 15 8 5/8' 329' w/250 sacks
 12 6
 13 5
 4 1/2' 4537' w/250 sacks

ELEVATION

PRODUCTION

Oil

FIGURES INDICATE BOTTOM OF FORMATIONS

75 Post Rock
 330 Shale
 1840 Shale & Shells
 1856 Red Bed
 1885 Anhydrite
 1990 Shale & Shells
 2300 Shale
 2930 Lime & Shale
 3030 Lime
 3225 Lime & Shale
 3315 Lime
 3335 Lime & Shale
 3400 Shale & Lime
 3905 Lime & Shale
 4470 Lime
 4514 Lime - Miss.
 4525 Lime w/Chert
 4540 Mississippi
 4540 NTD

RECEIVED
 STATE CORPORATION COMMISSION

NOV 2 1964

CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas
 County of Sedgwick }

I, W. H. Wurfin of the Wurfin Drilling Company Company

upon oath state that the above and foregoing is a true and correct copy of the log of the D. V. Smith well.

W. H. Wurfin
 W. H. Wurfin

Subscribed and sworn to before me this 10th day of July 19 63

ADELA MIZENER, Notary Public
 My Commission Expires My commission expires November 5, 1966

Adela Mizener
 ADELA MIZENER
 NOTARY PUBLIC