

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 34 Twp. 18 Rge. 26 (X) (W)

Location as "NE/CNW/SE/SW" or footage from lines C-NE-SW-NE

Lease Owner Cooperative Refinery Association

Lease Name Pember A Well No. 1

Office Address Box 765 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed December 12 19 55

Application for plugging filed December 11 19 55

Application for plugging approved December 12 19 55

Plugging commenced December 12 19 55

Plugging completed December 12 19 55

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundage

Producing formation Depth to top Bottom Total Depth of Well 4430 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	83'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug at 250'. Cemented with 35 sacks cement. Top plug set at 35'. Cemented with 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Company Rig #5
Address Box 765 Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, ss.
John H. Nation (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Nation
Box 765 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15 day of December 1955
Ruth Whove

My commission expires Sept. 2, 1959 Notary Public.

PLUGGING
FILE SEC 34 T 18 R 26 W
BOOK PAGE 23 LINE 35

12-16-55

DRILLERS LOG

Pember A #1

Loc: C-NE-SW-NE
 Sec: 34-18-26W
 Ness County, Kansas
 Operator: Cooperative Refinery Ass'n.
 Contractor: Company Rig #5

Elevation: 2464' D.F.
 Casing: 8 5/8" @ 83' with 100 sx.
 Comm: 11-25-55 Comp: 12-12-55
 Total Depth: 4430'.

<u>From</u>	<u>To</u>	<u>Formation</u>
0	83	Surface hole
83	350	Shale and shells
350	1150	Shale, sand shells
1150	1790	Shale and shells
1790	1945	Shale, shells, red bed
1945	2500	Lime and shale
2500	2880	Lime
2880	3600	Lime and shale
3600	3710	Lime
3710	3785	Lime and shale
3785	3935	Lime
3935	3995	Lime and shale
3995	4345	Lime
4345	4389	Lime and shale
4389	4430	Lime
4430		R.T.D.

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Pember A #1 well, located C-NE-SW-NE of Section 34-18-26W, Ness County, Kansas.

Subscribed and sworn to before me this 14 day of December 1955.

John H. Watson

Ruth W. Love

My commission expires: September 2, 1959

PLUGGING
 FILE SEC 34 T 18 R 26W
 BOOK PAGE 33 LINE 35

RECEIVED
 DEPARTMENT OF REVENUE
 BARTON COUNTY