15-135-20881-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD

Ness County. Sec. 29 Twp. 18 Rge. 26 (E) ___ (W) X

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNWKSWK" or footage from lines SE NE
Lease Owner Will P. Ash
Lease Name Reeves Well No. #1
Office Address 507 Rutland Wichita, Kansas 67206
Character of Well (completed as Oil, Gas or Dry Hole) ___
Date well completed ___ 19___
Application for plugging filed ___ 19___
Application for plugging approved ___ 19___
Plugging commenced 9-2-75 19___
Plugging completed 9-5-75 19___
Reason for abandonment of well or producing formation ___

If a producing well is abandoned, date of last production ___ 19___
Was permission obtained from the Conservation Division or its agents before plugging was commenced? ___

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation ___ Depth to top ___ Bottom ___ Total Depth of Well 4551' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5½"	4549'	1847.36'
				8 5/8"	332'	

STATE CORPORATION COMMISSION
SEP 08 1975
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet for each plug set.

Made bottom hole plug back with sand to 4525'. Mixed and ran 4 sacks cement thru dump bailer.
Pump 20 sacks gel - 1 sack hull - 70 sacks cement 50/50 pozmix with 6% gel.
10 sacks gel. Release plug 70 sacks cement 50/50 pozmix with 6% gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec

Box 364 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of Sept. 19 75

Sidney D. Miller
Notary Public.

My commission expires 24 October 1976

SIDNEY D. MILLER
NOTARY PUBLIC
BARTON COUNTY, KANSAS

KANSAS GEOLOGICAL SOCIETY 15-135-20881-0000

KANSAS WELL LOG BUREAU — KANSAS WELL SAMPLE BUREAU

KANSAS GEOLOGICAL SOCIETY BUILDING

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Will P. Ash


SEC. 29 T. 18S R. 26W

FARM Reeves NO. 1

LOC. SE NE

COUNTY Ness

KANSAS



TOTAL DEPTH 4,551'

COMM. December 2, 1974 COMP. December 13, 1974

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED

CASING

20 10

15 8 -5/8" 332' cemented w/185 sxs cement ELEVATION 2,560 GR

12 6

13 5½" 4,549' cemented w/275 sxs cement PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay, Post Rock, Sand and Shale	332'
Shale and Sand	1,235'
Red Bed	1,330'
Anhydrite	1,345'
Red Bed and Sand	1,645'
Shale	1,929'
Anhydrite	1,966'
Shale, Red Bed and Shells	2,425'
Shale and Lime	2,795'
Lime and Shale	2,960'
Shale and Lime	3,573'
Lime and Shale	4,075'
Lime	4,551'
Rotary Total Depth	4,551'

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1975
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 16th. day of December, 1974.

ELSIE WILLISON NOTARY PUBLIC SEDGWICK COUNTY, KANSAS

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
June 30, 1978