

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 27 Twp. 18S Rge. (E) 26 (W)

Location as "NE/CNW&SW&" or footage from lines C NE SW
Lease Owner Clinton Oil Company
Lease Name Orvil Edwards Well No. 1-V
Office Address 217 North Water, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 7, 19 72
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced August 7, 19 72
Plugging completed August 7, 19 72
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Leo Massey of Hays)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	363'	8-5/8"	363'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 720 Feet,
70 sax Cement Plug; Mud to 300 Feet,
20 sax Cement Plug; Mud to 40 Feet,
1/2 sax Halls, Plug Bridged & 10 sax
Cement to Base of Cellar; 2 sax in
Rat Hole. Job completed @ 6 P.M.

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1972
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing
Address Box 169, Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Clarence Michael of Sage Drilling Co. (owner or operator) of the above described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 8th day of August, 1972.



Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1974.

15-135-20641-0000

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1972
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

ORVIL EDWARDS NO. 1-V

CASING RECORD:	OPERATOR: Clinton Oil Company	DESCRIPTION:
8-5/8" @ 363' w/250 sax cement	CONTRACTOR: Sage Drilling Co.	C NE SW Sec. 27-18S-26W Ness Co., Kansas
TOTAL DEPTH: 4500'	COMMENCED: July 29, 1972	ELEVATION: 2528KB
	COMPLETED: August 7, 1972	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Top Soil, Post Rock & Shale	0	265	
Shale	265	530	
Shale & Red Bed	530	1150	
Red Bed & Shale	1150	1800	
Anhydrite	1800	1835	
Shale, Red Bed & Lime	1835	2415	
Shale & Lime	2415	2545	
Lime & Shale	2545	4000	
Lime	4000	4200	
Lime & Shale	4200	4248	
Lime	4248	4500	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 8th day of August, 1972.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.