

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-22,699-0000

LEASE NAME McJunkin

WELL NUMBER 1

SPOT LOCATION NENESE

SEC. 5 TWP. 20RGE. 21 (R) or (W)

COUNTY Ness

Date Well Completed 11-2-84

Plugging Commenced 8:00 AM

Plugging Completed 11:30 AM  
11-2-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Dreiling Ltd of Colorado  
ADDRESS 410 - 17th St., Suite 1140, Denver, Co. 80202

PHONE # (303) 623-6144 OPERATORS LICENSE NO. 5804

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Richard Lacey

Is ACO-1 filed? Yes If not, is well log attached? No logs taken

Producing formation None Depth to top \_\_\_\_\_ bottom T.D. 4462

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippian	165' mud with oil speck thru- out	4426	4456	8-5/8	369	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Hole full of heavy mud--51 vis. Pumped cement through drill pipe as follows:

- 1st cement plug at 1530' with 50 sacks
  - 2nd cement plug at 750' with 50 sacks
  - 3rd cement plug at 420' with 50 sacks
  - 4th wood & rubber 8-5/8" plug with solid hull bridge at 40' with 10 sacks
- (If additional description is necessary, use BACK of this form.)

*(See Back of Form)*

Name of Plugging Contractor Halliburton License No. 5287  
Address Hays, Kansas

C&R Drilling Co Serry Horton - Pusher

STATE OF Colorado COUNTY OF Denver, ss.

Les Olson (employee of operator) or

(operator) of above-described well, being duly sworn on oath, says: That I have knowledge of the facts, state and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

NOV 14 1984

(Signature) Les Olson

(Address) 410 17th St., Suite 1140  
Denver, Colorado 80202

CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1984

Barbara C. Murphy  
Notary Public

My Commission expires: 9-2-87

10 sacks in mousehole

10 sacks in rathole

180 sacks total sacks of cement 60/40 pozmix 2% gel, 3% cc